

South Long Park Sports Court project description:

Provide Paving and equipment installation for a new Basketball and Tennis Court measuring 60-ft wide by 215-ft long including Sports Court Markings and Striping for multiple games. The Tennis Court shall include a 10-ft high, black enamel coated chain link fence (with gates) on 3 sides with the fourth side connecting to a 20-ft wide, 16-ft high cast-in-place concrete handball wall.

A full set of construction documents prepared by Tredo Engineers (dated 5/27/21) shall be the basis the contract.

The successful bidder shall be responsible for:

- Excavation & Backfill for New Handball Wall Foundation
- Form and Cast New Concrete Handball Wall
- Fine Grade Stone subbase for new asphalt paving
- Asphalt Paving - Binder: according to the plans and specs. Roll to a smooth even finish. (assume 1<sup>st</sup> mobilization for Binder)
- Asphalt Paving - Top: according to the plans and specs. Clean and tack the binder prior to paving. Roll to a smooth even finish. (assume 2<sup>nd</sup> mobilization for Top)
- Supplemental Paving for relocated walkway south of Tennis Court
- Sports Court Markings & Surfacing: Stripe & color surface the new courts as shown on plans.
- Fencing around Tennis Court
- Install Sports Equipment including (4) Basketball nets and (1) adjustable Tennis net with light (furnished by Village)
- Coordinate with Village DPW

The Village DPW will be responsible for:

- Site Demolition
- Site Electric
- Site Plumbing (water fountain)
- Site Drainage Improvements/Modifications
- Site Grading within +/- 1" for Sports Court subbase
  - Line & grade for edge of pavement
- Installation of Water fountain
- Topsoil and Seed

The relocation of the existing Park Shelter and the installation of the proposed Park Shelter are both excluded from this contract.

All workers shall be fully licensed and insured and shall be remunerated based on prevailing wage rates in accordance with Village municipal purchasing standards. Price shall be based on performing work Monday thru Friday during normal working hours (7am to 5pm). Permits are the responsibility of the Village. Should the successful bidder encounter unforeseen underground obstacles, the removal of such obstacles shall be by Village DPW at no expense to the contractor. The Village will make suitable truck access to the building site.

The project shall be completed prior to November 1<sup>st</sup>, however if there will be a significant benefit to postpone the project until Spring 2022, the Village will entertain bid/schedule alternates to improve participation in this solicitation and the cost efficiency of the project.